Public Works Equip Co
2 Taylor Boulevard
Box 1006
New Kingstown, PA 17072
(717) 697-8045
(717) 697-0154 fax

QUOTATION

No.	PWE137
Date	3/11/97
Terms	Net 30 Days
FOB	Millersville
Delivery	60 Days
Salesman	Rick Moyer

To: Millersville Borough
10 Colonial Avenue
Millersville, PA 17551

We are pleased to quote as follows:

2110C VACTOR JET RODDER (1996 DEMONSTRATOR UNIT AS SPECIFIED)

Standard Equipment:

10 CUBIC YARD CAPACITY CATCH BASIN CLEANER AND SEWER CLEANER
1997 Ford LN8000 210 HP Allison MD3050 Automatic Transmission
Cummins Diesel Engine with Hi Temp-Low Oil Pressure Shutdown
Sliding Engine Noise Shroud
38" Aluminum centrifugal compressor
Twin disc overcenter clutch
Gear type step-up transmission to operate compressor
Vactor variable pressure water pump hydraulically driven 60 GPM at 2,000 PSI
600 foot capacity hose reel with 500 feet of 1 inch 2,500 operating & 6,250 burst pressure rodder hose
Double acting hydraulic dump hoist
Complete Nozzle Package for Multi-Flow System
Electric over hydraulic four-way power boom assembly with 180 degree rotation
Remote push button pendant control with 50 feet of cable
Standard pipe package consists of:
- (1) 3 foot aluminum pipe extension
- (3) 5 foot aluminum pipe extension
- (1) 7 foot catch basin nozzle
- (4) 8 inch overcenter quick clamps with gaskets

Full opening rear door hinged at the top
Body drain on rear door with 6 inch drain hose
Variable flow handgun assembly with 25 feet of 1/2 inch drain hose with couplings front and rear
Sealed electrical system
1,000 gallon aluminum water tank assembly
Hydraulically tilting hose reel asembly
Catch basin cleaning water system providing 20 GPM at 600 PSI through 1/2 inch hose
Water pump overspeed controls
Flexible hose guide
Mud Flaps
Vactor Parts & Service Manual
Operator Training
Paint Module
Delivery

	Standard Equip. Price	$154,852.00
See Detail on next page ——————>	Optional Equip. Price	$0.00
	Budget Price	**$154,852.00**

Public Works Equip Co
2 Taylor Boulevard
Box 1006
New Kingstown, PA 17072
(717) 697-8045
(717) 697-0154 fax

QUOTATION

No.	PWE137
Date	3/11/97
Terms	Net 30 Days
FOB	Millersville
Delivery	60 Days
Salesman	Rick Moyer

Optional Equipment:and Accessories:

Part	Description
VS170	1" - 15 degree Sanitary Nozzle (6 Rear, Tungsten Carbide Inserts)
VS160	30 degree Sanitary Nozzle (6 rear orifices Tungsten Carbide)
VS040	Aluminum Storm Nozzle #10 with 8 replaceable nozzles
VP110	Module w/Amershield Polyurethane (White Only/Match Cab)
V9015	45x14x12 Weatherproof Tool Box
V9003	Electronic Back-Up Alarm
V9002	Tow Hooks, Per Set
V8013	Limb Guard for Light
V8004	Revolving Light
V8002	Handlight w/Bumper Plug
V8000	Circuit Breakers
v6014A	Aero-Style Tele/Rotating Hose Reel (600' Capacity)
V6005	Hose Footage Counter
V6004	Hose Level Wind Guide (Dual Roller)
v6001A	500' x 1" Shark Sewer Hose-3000 PSI
V5012	Multi-Flow System for Water Pump (Inc. 2 Nozzles & Rack)
V5010	Accumulator System for Water Pump
V5008	Cold Weather Recirculation System-Dual Engine Units
V5003	80 GPM/2500 PSI Water System - Standard
V4006	Joystick Boom Control (Standard Boom or Tele/Ext Boom)
V4005	Boom Transport Cradle - Standard
V4004	8 ft. Hydraulic Telescopic Boom w/180 deg. Hyd. Rotation
V3002	Single Stage Vacuum System (1.6 Step-Up w/Perkins/Funk)-Standard
V1015A	Fold Down Pipe Rack/Streetside
V1015	Fold Down Pipe Rack/Curbside
V1012	6" Decant System w/Valve and w/Screen
V1006	5" Butterfly Valve in Rear Door
V1005	Stainless Steel Ball Float Shut-Off
V1003	Debris Body Flushout System
V1001	Hydraulic Rear Door Locks

	Optional Equip. Price	$0.00
See Detail on previous page ——————>	Standard Equip. Price	$154,852.00
	Budget Price	**$154,852.00**